

EMCAL report to Temple

Y. Kubota

5/22/04

Outline

- Intro – definition of “staged”
- Project flow
- Critical path and schedule
- Labor, cost profiles
- Installation
- CD-1 recommendations and responses
- Risk management

Intro

- 10,100 PWO crystals of $28 \times 28 \times 220 \text{ mm}^3$
 - Tyvek wrapped
- PMT – 5-7 stages, gain 3000, requiring 7 HV's provided separately (no local voltage divider) daisy chaining 100 of them.
- Signal cable to FEB 2-4m
- Support structure has cells for individual crystals.
- Light pulser/optical fibers to test system and calibrate crystals.

Staged

- 1st stage has half as many crystals (~5000)
- Typical efficiency (compared to the full detector) is ~60%.
 - Near the beam pipe (not right next to it) there are more photons
- More crystals will be installed as long as their delivery is on schedule.

Project Flow





Fig. 1 Project Flow diagram and key dates

Critical Paths – Schedule floats

	Ready by	Need by	Floats
Support structure	Dec 27, 2007	Aug 27, 2008	168 days
20% of crystals-PMT's	Dec. 28, 2008	Dec 1, 2008	232 days
50% of crystals-PMT's	Apr. 11, 2008	Sept. 7, 2009	353 days
75% of crystals-PMT's	Nov. 28, 2008	July 1, 2010	397 days
100% of crystals-PMT's	Sep. 24, 2009	Aug. 2, 2010	212 days



Labor Profile




Fig. 2 Labor profile

Cost

- Total \$12.5M base - \$16.7M w/ contingency (33.6%)
- M&S \$10M base
- Labor \$2M
- \$300k increase of CD-1 (Chinese crystal production accelerated)

Cost Profile




Fig. 3 Cost Profile

Change from CD-1

Cost profile changes




Fig. 5 Cost changes from CD-1

Obrowser view

Activity ID	Activity Name	Material(\$)	Labor(\$)	Base Cost(\$)	Material Contingency(%)	Labor Contingency(%)	Total FY05	Total FY06	Total FY07	Total FY08	Total FY09	Total FY05-09
1.4.1	Detector - PWO Crystals	6,093,310	93,752	6,187,062	40	30	55,146	384,831	1,153,295	2,933,106	0	4,526,378
1.4.2	Detectors - PMT's bases	2,149,969	141,332	2,291,301	28	24	2,525	203,353	1,337,638	1,358,152	0	2,901,668
1.4.3	EMCAL Electronics and Associated Infrastructure	1,510,739	639,067	2,149,806	30	30	387,907	469,960	1,925,088	10,111	0	2,793,065
1.4.4	Mech Air and Temperature ctrl Systems	402,561	600,452	1,003,013	20	24	0	654,561	227,616	291,286	0	1,173,463
1.4.5	Integration and Testing	114,542	460,324	574,866	26	32	4,376	662,986	76,653	8,933	0	752,946
1.4.6	EM Calorimeter Detector Subproject Management	67,975	191,024	258,999	38	25	43,353	77,248	73,697	107,282	0	301,581
1.4	Subproject 1.4	10,339,095	2,125,951	12,465,046	35	28	493,307	2,452,939	4,793,987	4,708,869	0	12,449,101

Installation in C0

- i. move the support structure, with crystals partially loaded and tested, from the Assembly Hall to C0
- ii. light pulsers and front-end electronics (FEB) near the detector
- iii. Load crystals (PMT's attached)
- iv. Connect optical fibers, signal cables and HV cables
- v. Connect FEB's to DAQ
- vi. Repeat (iii) and (iv) above in 2010. (v) too?

Installation labor

- 5.5 FTE
 - 4 FTE – physicists
 - 1 FTE – technicians
 - 0.5 FTE – engineers (ME & EE)

CD-1 recommendations

- Explore ways to arrive at a schedule with comfortable float (>6 months) by working with BTeV Management and Installation & Integration group.
 - Staged installation of EMCAL is our answer to this recommendation. We now have a minimum of 169 business days (> 6 months) of floats.
- Add an Installation Engineer to the project.
 - More engineering is being added as a shared resource to the Project Office.
- Add US collaborators
 - Yes, we are trying.

Default schedule

No CMS interference - default Chinese production capacity




Fig. 4 Schedule of crystal and PMT acquisition and their installation

Risk - mitigation

- Acquisition of crystals with only a few manufacturers can be risky.
- CMS narrowed the vendor field to one fairly early in their process.
 - We will keep at least two vendors in the race.

If CMS is in our way

If CMS uses SIC, delaying BTeV production, but boosting production capacity at SIC




Fig. 6: alternative crystal production schedule in case vendors are busy with CMS crystal production until mid-2007.