




BTeV Muon (WBS 1.5)

Will Johns ~ Vanderbilt University







Institutions & People



Illinois

- Mats Selen
- > Jim Wiss
- Doris Kim
- ➤ Mike Haney
- Vaidas Simaitas

Puerto Rico

- > Angel Lopez
- > Hector Mendez
- **Eduardo** Ramirez
- > Zhong Chao Li
- > Aldo Acosta

Vanderbilt

- > Will Johns
- > Paul Sheldon
- ➤ Med Webster
- > Eric Vaandering
- > John Fellenstein

Legend:

Engineer






Goals & Constraints



- Provides Muon ID and Trigger
 - Trigger & ID for interesting physics states
 - Check/debug pixel trigger
- Fine-Grained tracking + toroids
 - Stand-alone mom./mass trig.
 - Momentum "confirmation" (improves background rej.)

- Other design goals/constraints:
 - Min. pattern recognition confusion
 - Minimize occupancy
 - Distribute occupancy uniformly
 - > Minimize max. drift time
 - > Robust, high-rate detector element
 - Size of hall limits wide-angle acceptance to 200 mrads





Basic Building Block



- Basic Building Block: Proportional Tube "Planks"
 - > 3/8" diameter Stainless steel tubes (0.01" walls)
 - "picket fence" design
 - > 30μ (diameter) gold-plated tungsten wire
 - > Brass gas manifolds at each end (RF shielding important!)
 - > Front-end electronics: use Penn ASDQ chips, modified CDF COT card
 - ➤ Likely to use 85% Ar 15% CO₂ (no CF₄... more on this later)





Geometry


IP

B B F



- Min. pattern recognition confusion
- > Reduce occupancy
- Distribute occupancy uniformly
- Minimize max. drift time
- > Robust, high-rate detector element
- Stand-alone momentum/mass trigger
- Momentum "confirmation" (improves background rejection)
- Meets reqd. tracking resolution (<2mm)</p>

12 planks "cover" each octant



Beams Eye View of each station: overlapping octants

stereo views provide ϕ info.


4 views per station (r, u, v, r)



Installation Unit: Octant (or Quad)



- 4 octants make a wheel, two wheels construct a view.
- Octants will be built at institutions and delivered to FNAL.
- "Vertical Lazy Susan" installation - rotate during installation on floor rollers
- Each wheel will then be hung vertically from overhead beams.
- This allows each view to be individually serviced: it will be possible to install and/or remove an octant during run.
- Each octant is installed in wide aisle horizontally.



U - stereo wheel plates.



Prototype Wheel and Quad






Directors CD-2/3a Review of the BTeV Project – Sept. 28-30, 2004 BTeV Muon System (WBS 1.5) – Will Johns



Overhead Support





- The entire muon system can move with the toroid package since there are no floor connections.
- The wheels are supported from individual floor rollers during installation and then hung vertically from the overhead beams.





Expected Occupancies



- Minimum bias events will be largest source of hits in detector
- Generated assuming an average of 2 interactions/crossing
 - \triangleright OLD Luminosity of $2x10^{32}$ and 132 ns bunch spacing

What	Station 1	Station 2	Station 3	Total
avg. # of hits per crossing	42	8	9	54
avg. occupancy	0.34%	0.06%	0.07%	0.15%
max. channel occupancy	2.50%	0.24%	0.52%	
max. channel rate (kHz/cm^2)	3.7	0.4	0.8	








Organization




Base cost: \$3.81M (Material: \$2.93M, Labor: \$0.88M)





Organization







Construction Cost




Activity ID	Activity Name	Base Cost (\$)	Material Contingency (%)	Labor Contingency (%)							Total FY05-10
	Muon Detector Planks	1,788,686	43	35	203,104	908,305	1,054,901	354,960	0	0	2,521,269
1.5.2	Muon Detector Stations	350,771	40	35	63,436	246,290	136,397	41,013	0	0	487,136
	Muon Detector Electronics	1,341,849	41	17	40,118	885,865	415,335	510,614	0	0	1,851,933
1.5.4	Muon Detector Test Stands	156,726	45	50	65,448	42,949	119,421	0	0	0	227,818
	Muon Detector Gas System	121,319	50	0	0	106,050	66,903	0	0	0	172,953
1.5.6	Muon Detector Software	0	0	0	0	0	0	0	0	0	0
	Muon Detector Subproj Mgmt	669,276	24	24	115,275	238,882	238,882	238,882	0	0	831,920
1.5	file_15_092104	4,428,627	41	28	487,380	2,428,341	2,031,839	1,145,468	0	0	6,093,029



M&S Cost Profile by Fiscal Year








Labor Profile by Fiscal Year








Description of Project Flow








Key Milestones With Distributed Float







CD-1 Recommendations



- The primary recommendation was that we hire a full-time quality assurance engineer for the duration of the project.
 - After discussing this with project management, it was decided that additional effort will be added to the project office to handle QA issues for BTeV. The muon project will hire a full-time technician to handle QA and project oversight.
 - ➤ We have added this technician to our WBS
- Actively pursue forward funding.
 - ➤ Vanderbilt has verbally agreed to provide \$1M in forward funding. MOU is in preperation.





The End



Required Backup Slides



The next two slides are required



Glossary of Terms



■ These should be terms that are BTeV jargon or really unusual technical terms. If you use a glossary at the end, indicate its presence clearly in a box on slide 3, so reviewers will know that it is there for them to peek at during the talk.



Description of Project Flow With Distributed Float



