




### BTeV Muon (WBS 1.5)

Paul Sheldon ~ Vanderbilt University







#### Institutions & People



#### Illinois

- Mats Selen
- > Jim Wiss
- Doris Kim
- ➤ Mike Haney
- Vaidas Simaitas

#### **Puerto Rico**

- ➤ Angel Lopez
- > Hector Mendez
- **Eduardo** Ramirez
- Zhong Chao Li
- > Aldo Acosta

#### Vanderbilt

- > Will Johns
- > Paul Sheldon
- ➤ Med Webster
- > Eric Vaandering
- > John Fellenstein

#### Legend:

Engineer






#### Goals & Constraints



- Provides Muon ID and Trigger
  - Trigger & ID for interesting physics states
  - Check/debug pixel trigger
- Fine-Grained tracking + toroids
  - Stand-alone mom./mass trig.
  - Momentum "confirmation" (improves background rej.)

- Other design goals/constraints:
  - ➤ Min. pattern recognition confusion
  - Minimize occupancy
  - Distribute occupancy uniformly
  - > Minimize max. drift time
  - > Robust, high-rate detector element
  - Size of hall limits wide-angle acceptance to 200 mrads





#### **Basic Building Block**




- Basic Building Block: Proportional Tube "Planks"
  - > 3/8" diameter Stainless steel tubes (0.01" walls)
  - "picket fence" design
  - > 30μ (diameter) gold-plated tungsten wire
  - Brass gas manifolds at each end (RF shielding important!)
  - > Front-end electronics: use Penn ASDQ chips, modified CDF COT card
  - ➤ Likely to use 85% Ar 15% CO<sub>2</sub> (no CF<sub>4</sub>)





#### Geometry





#### Meets design goals/constraints:

- ➤ Min. pattern recognition confusion
- > Reduce occupancy
- Distribute occupancy uniformly
- Minimize max. drift time
- > Robust, high-rate detector element
- Stand-alone momentum/mass trigger
- Momentum "confirmation" (improves background rejection)
- Meets reqd. tracking resolution (<2mm)</p>

# 12 planks "cover" each octant 2 st

Beams Eye View of each station: overlapping octants

2 stereo views provide  $\phi$  info.

4 views per station (r, u, v, r)



#### Installation Unit: Octant (or Quad)




- 4 octants make a wheel, two wheels construct a view.
- Octants will be built at institutions and delivered to FNAL.

"Vertical Lazy Susan" See movie!
 installation - rotate during
 installation on floor rollers

 Each wheel will then be hung vertically from overhead beams. (picture later)

 This allows each view to be individually serviced: it will be possible to install and/or remove an octant during run.

 Each octant is installed in wide aisle horizontally.



U - stereo wheel plates.



#### Prototype Wheel and Quad






DOE CD-2/3a Review of the BTeV Project – Dec. 14-16, 2004 BTeV Muon System (WBS 1.5) – Paul Sheldon



#### Overhead Support





- The entire muon system can move with the toroid package since there are no floor connections.
- The wheels are supported from individual floor rollers during installation and then hung vertically from the overhead beams.





#### **Expected Occupancies**



- Minimum bias events will be largest source of hits in detector
- Generated assuming an average of 2 interactions/crossing
  - > Updating these studies now...

What	Station 1	Station 2	Station 3	Total
avg. # of hits per crossing	42	8	9	54
avg. occupancy	0.34%	0.06%	0.07%	0.15%
max. channel occupancy	2.50%	0.24%	0.52%	
max. channel rate (kHz/cm^2)	3.7	0.4	0.8	








#### Organization








#### Organization







#### **Construction Cost**




Activity ID	Activity Name	Base Cost (\$)	Material Contingency (%)	Labor Contingency (%)							Total FY05-10
	Muon Detector Planks	1,788,686	43	35	203,104	908,305	1,054,901	354,960	0	0	2,521,269
1.5.2	Muon Detector Stations	350,771	40	35	63,436	246,290	136,397	41,013	0	0	487,136
	Muon Detector Electronics	1,341,849	41	17	40,118	885,865	415,335	510,614	0	0	1,851,933
1.5.4	Muon Detector Test Stands	156,726	45	50	65,448	42,949	119,421	0	0	0	227,818
	Muon Detector Gas System	121,319	50	0	0	106,050	66,903	0	0	0	172,953
1.5.6	Muon Detector Software	0	0	0	0	0	0	0	0	0	0
	Muon Detector Subproj Mgmt	669,276	24	24	115,275	238,882	238,882	238,882	0	0	831,920
1.5	file_15_092104	4,428,627	41	28	487,380	2,428,341	2,031,839	1,145,468	0	0	6,093,029



#### M&S Cost Profile by Fiscal Year








#### Labor Profile by Fiscal Year








#### Technical Labor Profile by Fiscal Year








#### Physicist Labor Profile by Fiscal Year








#### Description of Project Flow








#### **Key Milestones**







#### CD-1 Recommendations




- The primary recommendation was that we hire a full-time quality assurance engineer for the duration of the project.
  - After discussing this with project management, it was decided that additional effort will be added to the project office to handle QA issues for BTeV. The muon project will hire a full-time technician to handle QA and project oversight.
  - ➤ We have added this technician to our WBS
- Actively pursue forward funding.
  - ➤ Vanderbilt has verbally agreed to provide \$1M in forward funding. MOU is in preparation.



#### Significant Experience



- We have significant experience w/ many of the steps necessary to build and install the muon system
  - Built roughly 2 dozen planks, with student labor
  - Designed, built and used many of the test stands that we will use in our quality assurance program (tension measurement, etc.)
  - Built a full scale model of one wheel, using it to investigate support and installation issues
  - During the past year, significant engineering on mechanical support structure, now have a well-developed design
  - We have a well-developed design for the Front-End electronics and we have verified its properties with prototypes





#### **Concluding Remarks**



- We have dealt with many of the vendors we will use
  - ➤ Vanderbilt shop has fabricated the parts it has to make
  - > Stainless tube vendors, ...
  - ➤ Penn ASDQ's
- The labor required is modest (43 FTEs) and well-matched to the size of the research groups already on-board.
  - > Physicist ("off-project") labor reqd is already present in our groups
  - > student labor required is not larger than is typically present in each of our groups
- We have chosen a robust, easy to build, well understood detector technology and our studies indicate that it is well matched to our problem.
  - ➤ This includes a well-developed and engineered design for the mechanical structure and support






# The End



## Description of Project Flow With Distributed Float







#### Key Milestones With Distributed Float



