

BTeV Muon (WBS 1.5)

Paul Sheldon ~ Vanderbilt University



- Institutions
- Requirements
- Design
- Project Management
- Costs and Labor
- Schedule and Major Milestones
- FY05 Activities
- Concluding Remarks

■ Illinois

- Mike Haney
- Vaidas Simaitas
- Mats Selen
- Jim Wiss
- Doris Kim

Legend:

Engineer
Faculty
PostDoc
Technical

■ Puerto Rico


- Angel Lopez
- Hector Mendez
- Eduardo Ramirez
- Zhong Chao Li
- Aldo Acosta


■ Vanderbilt


- Will Johns
- Paul Sheldon
- Med Webster
- Eric Vaandering
- John Fellenstein



- Provides Muon ID and Trigger
 - Trigger & ID for interesting physics states
 - Check/debug pixel trigger
- Fine-Grained tracking + toroids
 - Stand-alone mom./mass trig.
 - Momentum “confirmation” (improves background rej.)
- Requirements & Characteristics
 - 2 mm position resolution
 - Trigger: 500:1 min bias rejection, 80% efficiency for di-muon events
 - 200 mrad maximum acceptance (set by size of hall), 40 mrad minimum (set by beam components)
 - Stations at 9.4, 10.8, & 12 m from IP




- Basic Building Block: Proportional Tube “Planks”
 - 3/8” diameter Stainless steel tubes (0.01” walls)
 - “picket fence” design 
 - 30 μ (diameter) gold-plated tungsten wire
 - Brass gas manifolds at each end (RF shielding important!)
 - Front-end electronics: use Penn ASDQ chips, modified CDF COT card
 - Likely to use 85% Ar - 15% CO₂ (no CF₄)
 - Robust, high-rate detector element





Planks will be built at UI,
UPR, & VU (527 ea)

- We want to observe tracks in 3 disk shaped ***stations*** 2.4 m in radius:
 - Minimum pattern recognition confusion
 - Minimize occupancy and distribute it uniformly





Beams Eye View of each station: divided into overlapping ***octants***






- 4 *octants* or *quads* make a *wheel*
- two *wheels* are required for full azimuthal coverage.
- Short planks at small radius minimize occupancy there.
- Octant geometry minimizes pattern recognition confusion








12 planks "cover" each octant



2 stereo views provide ϕ info.
4 views per station (r, u, v, r)
8 wheels per station




- Planks are mounted on an “exoskeleton” made of **100 mil** thick aluminum plates and stiffener bars
- Octants built at UI and VU and sent to FNAL.
- Top cover plate not shown!





- At **300 lbs.**, octants are light and small enough that handling them is relatively easy.






- The small size of the hall gives us little room above or on one side of the detector.
- There is no overhead crane in the hall.
- This has forced us to be creative in designing our installation scheme!

- “Vertical Lazy Susan” **See movie!**
installation - rotate during
installation on floor rollers
- This allows each view to be
individually serviced: it will
be possible to install and/or
remove an octant during run.
- Each octant is installed in
wide aisle horizontally. 
- Each wheel will then be hung
vertically from overhead
beams. (next slide...)








- The entire muon **system** can move with the toroid package since there are no floor connections.
- The toroid assembly is a separate sub-project (WBS 1.1). We have excellent communication with that project regarding space constraints, installation and integration.

■ Base Numerology

- 3 stations
- 4 views per station
- 8 octants per view
- 12 planks per octant
- 32 tubes per plank
- Wheel = 4 octants
- 2 pre-production wheels
- 16 spare octants



■ For Full Detector:



- 36864 channels of tubes
- 1152 planks
- 96 quads

■ Including pre-prod & spares

- 46080 channels of tubes
- 1440 planks
- 120 quads


- Minimum bias events will be largest source of hits in detector
- Assuming an average of 6 interactions/crossing

What	Station 1	Station 2	Station 3	Total
avg. # of hits per crossing	126	24	27	162
avg. occupancy	1.01%	0.18%	0.21%	0.45%
max. channel occupancy	7.50%	0.72%	1.56%	
max. channel rate (kHz/cm ²)	3.7	0.4	0.8	



Base cost, fully burdened, in FY05 dollars:
\$4.4M (M&S: \$3.2M, Labor: \$1.2M)

WBS 1.5 – Muon
Will Johns & Paul Sheldon





Fully burdened, in FY05 dollars


Activity ID	Activity Name	Base Cost (\$)	Material Contingency(%)	Labor Contingency(%)	Total FY05	Total FY06	Total FY07	Total FY08	Total FY09	Total FY10	Total FY05-10
1.5.1	Muon Detector Planks	1,788,686	43	35	224,448	1,038,534	947,131	309,512	0	0	2,519,625
1.5.2	Muon Detector Stations	350,771	40	35	63,436	330,190	52,498	41,013	0	0	487,136
1.5.3	Muon Detector Electronics	1,342,152	41	17	40,118	885,865	415,790	510,614	0	0	1,852,387
1.5.4	Muon Detector Test Stands	156,726	45	50	65,448	42,949	119,421	0	0	0	227,818
1.5.5	Muon Detector Gas System	121,319	50	0	0	106,050	66,903	0	0	0	172,953
1.5.6	Muon Detector Software	0	0	0	0	0	0	0	0	0	0
1.5.8	Muon Detector Subproj Mgmt	600,916	24	24	30,262	238,882	238,882	238,882	0	0	746,907
1.5	file_15_07Dec04	4,360,570	41	28	423,711	2,642,470	1,840,623	1,100,021	0	0	6,006,826


WBS 1.5 Muon Detector M&S Obligation Profile


Fully burdened, in FY05 dollars












BTeV - WBS 1.5 Muon Detector Selected Key (Critical) Activities



- The primary recommendation was that we hire a full-time quality assurance engineer for the duration of the project.
 - After discussing this with project management, it was decided that additional effort will be added to the project office to handle QA issues for BTeV. The muon project will hire a full-time technician to handle QA and project oversight.
 - We have added this technician to our WBS
- Actively pursue forward funding.
 - Vanderbilt has agreed to provide \$1M in forward funding. Paperwork is in preparation.

- For FY05, we have scheduled only those Project Engineering and Final Design Activities necessary to keep the project on cost and schedule
- Begin our planned “pre-production” of ~100 planks and 8 octants.
 - Use to shake down our assembly lines and quality assurance programs at each institution
 - Train our QAP technician and assembly personnel
 - Make final design tweaks before production
 - This activity will begin in FY05 but not be complete until 3rd Qtr of FY06
- Costs are for parts needed, assembly jigs and hardware, test stands
 - Only those parts, test stands, etc., that are needed in FY05.
 - Quad test stand not purchased until FY06
- Have \$90K in R&D funds from NSF as well.

- We have significant experience w/ many of the steps necessary to build and install the muon system
 - Built roughly 2 dozen planks, *with student labor*
 - Designed, built and used many of the test stands that we will use in our quality assurance program (tension measurement, etc.)
 - Built a full scale model of one wheel, using it to investigate support and installation issues
 - During the past year, significant engineering on mechanical support structure, now have a well-developed design
 - We have a well-developed design for the Front-End electronics and we have verified its properties with prototypes

Tension Test Stand

File Settings Help

Single Tube Plank

Plank Barcode: 2010000100073 Enter Clear

Decoded Barcode: 2010000100073

Station: VU Tension Assembler: Eric Vaandering

Plank Length


☐ 30 cm ☐ 45 cm ☐ 60 cm ☐ 75 cm ☐ 90 cm ☐ 105 cm
☐ 120 cm ☐ 135 cm ☐ 150 cm ☐ 165 cm ☐ 180 cm ☐ 195 cm

Tube Number: 8

Central frequency [Hz]: 500

Calibrate Measure Tension Help

Ready to Measure

Barcode
tracking
system

- **We have dealt with many of the vendors we will use**
 - Vanderbilt shop has fabricated the parts it has to make
 - Stainless tube vendors, ...
 - Penn ASDQ's
- **The labor required is modest (43 FTE years) and well-matched to the size of the research groups already on-board.**
 - Physicist ("off-project") labor reqd is already present in our groups
 - student labor required is not larger than is typically present in each of our groups
- **We have chosen a robust, easy to build, well understood detector technology and our studies indicate that it is well matched to our problem.**
 - This includes a well-developed and engineered design for the mechanical structure and support
- **Technical Design is complete, although we anticipate a few tweaks.**

- **We have a well defined and complete Project Cost and Schedule**
 - **Significant float of over 460 days**
- **Sub-project management is in place and capable of performing the project**
- **MOU between Fermilab and Vanderbilt is complete and has been signed by all parties**
 - **Illinois and Puerto Rico MOUs in progress**
- **FY05 Project Engineering and Design work is essential to keeping the project on cost and schedule.**

The End

